

Background

- Lawn Avenue Parkette will be impacted due to utility realignment as a result of Stage 2 LRT construction, creating an opportunity to reinstate the parkette with the community's preferences in mind
- Previous consultations indicated the community required additional time to make decision on reinstatement options
- The preferred option will be reflected in the Stage 2 Confederation Line RFP October addendum

Lawn Avenue Parkette Drainage



Stormwater utility upgrades for both options consist of, but are not limited to:

- Clean, repair and re-grade ditches
- Re-grade the intersection of Edgeworth Avenue and Lawn Avenue towards the catch basin and inlets
- Provide a below-grade storm sewer beneath the Lawn Avenue Parkette and connect to Ottawa River Parkway Pipe (ORPP)

Option 1 – Landscaped with plantings



Option features:

1. Community garden to be located south of pathway
2. Park plaza with benches and low shrub planting
3. Generally flat grassed area with a variety of plantings

Option 2 – Integration of Rain Garden/Bioswale



This design aims to remove silt and pollution from surface water runoff

Option features:

1. Additional pathway entrance on west end of parkette
2. Community garden to be located north of west end pathway
3. Installation of a rain garden / bioswale

Next Steps

Please provide your completed comment sheet to a
Stage 2 Project Team member

or

email to Stage2@ottawa.ca by September 28, 2017

